Test Report No. 7191241095-MEC20-LXR dated 21 AUG 2020

Note: This report is issued subject to the Testing and Certification Regulations of the TÜV SÜD Group and the General Terms and Conditions of Business of TÜV SÜD PSB Pte Ltd. In addition, this report is governed by the terms set out



PERFORMANCE TEST

Add value. Inspire trust.

OF

SLIDING DOOR SYSTEM

FOR

PROJECT: Patio 130 IW (INOWA)

Roto Frank Asia-Pacific Pte. Ltd. **TESTED FOR:**

> 19 Joo Koon Road Singapore 628978

Attn: Qi Wei Hong

Lee Xi Ren PREPARED BY:

Associate Engineer

APPROVED BY: Ng Yui Xiong

Assistant Manager, Product

Building Group

Real Estate and Infrastructure-Mechanical Centre







LA-2007-0380-A LA-2007-0381-F LA-2010-0464-D LA-2007-0382-B LA-2018-0702-B LA-2018-0703-G LA-201

Report are not included in the SAC-

Laboratory: TÜV SÜD PSB Pte. No.1 Science Park Drive Singapore 118221

Phone: +65-6885 1333 +65-6776 8670 Fax: E-mail: enquiries@tuvsud.com https://www.tuvsud.com/ en-sg Co. Reg: 199002667R

Regional Head Office: **TÜV SÜD Asia Pacific** Pte. Ltd. 1 Science Park Drive, #02-Singapore 118221 TÜV

Test Report No. 7191241095-MEC20-LXR dated 21 AUG 2020



SUMMARY OF TEST AND TEST RESULTS PROJECT: PATIO 130 IW (INOWA)

Items	Project Test Parameters	Project Requirements	Results
Air Leakage Test	 a. Preload 50% design load (1350Pa) b. Operate sliding door 5 cycles. c. Apply positive pressure of 600Pa and record the air infiltration rate with polyethylene sheet pasted to test for extraneous leakage, Qe. d. Remove the polyethylene sheet. e. Apply positive pressure of 600Pa and record the specimen air leakage, Qts. 	Reference to ASTM E283-04 (2012) Nil Area = 5.3m ² Perimeter = 7m	Passed
Static Water Penetration Test	 a. Operate sliding door 5 cycles. b. Positive pressure of 1000Pa is applied for duration of 15 minutes on surface area. c. Record all points of water leakages. 	Reference to ASTM E331-00 (2016) No leakage is permitted onto the internal face of the sliding door system at a water spray of 3.4 L/m²/min.	Passed
Cyclic Water Penetration Test	 a. Operate sliding door 5 cycles b. Positive pressure of 600Pa is applied for duration of 5 minutes on surface area. c. Reduce pressure to 0Pa and maintain for 1 minute. d. Repeat b – c for pressure of 800, 1000, 1300Pa. e. Record all points of water leakages. 	Reference to ASTM E547-00 (2016) No leakage is permitted onto the internal face of the sliding door system at a water spray of 3.4 L/m²/min.	Passed
Structural Performance Test	 a. Preload 50% design pressure 1350Pa and maintain for 10 seconds. b. Between 1 to 5 minutes, take residual reading and zero transducers. c. Apply up to 100% design pressure of 2700Pa in 5 equal steps (1350, 1800, 2100, 2400 and 2700Pa) each 10 seconds and record the maximum deflection readings. e. Between 1 to 5 minutes, take residual deflection after load is removed. f. To be repeated for negative pressure (-2700Pa). 	Reference to AAMA TIR-11 Mullion/ Transom: maximum deflection shall not exceed Span/175 mm or 20mm whichever is lesser for spans less than 13 feet 6 inches 1-2-3 2650/175 15.14 mm 4-5-6 2000/175 11.43 mm Glass panels: 7-8-9 - For info 10-11-12 - For info	Passed
Proof Load Test	 a. Apply 150% design pressure i.e. 4050Pa and maintain for 10 seconds. b. Between 1 to 5 minutes, take residual reading and zero transducers. c. To be repeated for negative pressure (-4050Pa). 	Reference to ASTM E330/330M (2014) No permanent distortion or glass breakage shall occur. Hardware shall remain operable.	Refer to pg.10 for more details

Test Report No. 7191241095-MEC20-LXR dated 21 AUG 2020

